Project: REPAIRS OF POLYMERASE CHAIN REACTION (PCR Room) TESTING LABORATORY

Location College of Science and Mathematics, University of the Philippines Mindanao, Mintal, Davao City

Owner: Univerity of the Philippines Mindanao

Subject: Bill of Quantities/Cost Estimates

BILL OF QUANTITIES															
	Description	Qty	Unit		Equipment	I		Mark-ups	in Percent	Tota	al Mark Up	VAT	Total Indirect Cost	Total Cost	Unit Cost
Item No.				Material Cost		Labor Cost	Estimated Direct			1	Value				
	·	-			Rental Cost		Cost	OCM	Profit	%age	10	11	12	13	14
		1	2	3	4	5	6	7	8	9	7+8	12% x (5 + 10)	10+ 11	6 + 12	(13) / (1)
		·	-	Ū		Ū	0	12%	10%	Ű	110	5%		0112	(10)7(1)
2.0	ARCHITECTURAL WORKS							/.				0,0			
2.2	Repair of Glass Partition	12.74	sq.m												
	Framed Sliding Glass	12.74	sq.m												
	Silicone Sealant	1.00	lot												-
	Blind rivets	1.00	lot												
	Frosted Film design	50.00	sq.ft												1
2.3	NAME OF BOQ ITEM	4.65	sq.m												-
	PCR Room	4.65	sq.m												-
	Template Room	5.99	sq.m												
	Open Work Space	7.32	sq.m												
2.5	NAME OF BOQ ITEM	4.17	sq.m												
	2100mm x 600mm x 18mm thk Black Granite	1.00	рс												
	2100mm x 600mm x 18mm thk Black Granite	1.00	рс												
	2500mm x 600mm x 18mm thk Black Granite	1.00	рс	1											4
	3/4" Marine Plywood	12.00	sheets												+
	Stikwell	2.00	gals							+					+
	Silicon Sealant	2.00	tube							1					+
L	Common Nails	2.00	kls												+
	Misc (sand paper, etc)	1.00	lot												+
2.8	NAME OF BOQ ITEM	1.00	lot												
	(BOYSEN® Permacoat™ Flat Latex #701)	1.00	gals												
	(BOYSEN® Healthy Home™)	1.00	gals												
	Sandpaper	4.00	pcs												
	Waste Cotton	1.00	kg												
	Misc (thinner, brush, sand paper)	1.00	lot												
3.0	MECHANICAL WORKS														4
	AC unit Re-piping works (Refrigerant Piping system														
3.1	Copper Pipes - Soft drawn Type L)	1.00	lot												<u> </u>
	Split Type Airconditioning Units (Inverter type) 2.5 HP Split type Refrigerant Piping system Copper Pipes - Soft drawn	2.00	unit												
	15.9 mm (5/8") diameter x 15 m Length	2.00	roll												
	9.5 mm (3/8") diameter x 15 m Length	2.00	roll												+
	Consumables	1.00	lot												-
	Replacement/Repressurise Portable Existing Fire	1.00	101												+
3.2	Extinguisher	2.00	unit												
4.0	ELECTRICAL WORKS	2.00	dille												
4.0	Re-wiring works at PCR Room of Convenience Outlets														
4.1	and Ceiling Outlets	1.00	lot												
	5.5 mm 2 Thw Cu Wire	4.00	box			1									1
	3.5 mm 2 Thw Cu Wire	4.00	box												1
	3/4 dia Flexible hose "Orange"	2.00	roll			1									1
	Other electrical Fittings/Accessories (junction box,pull box) oct		lot												
	Bolt- on type Breaker (All Size)	1.00	lot												
	Panel Board	1.00	unit												
	Lighting Fixtures, Outlet and switches	1.00	lot												
	Other electrical fitting & accessories	1.00	lot												
	Steel conduit pipe	6.00	length												<u> </u>
	Weatherproof Utility Box with Cover	2.00	pcs												<u> </u>
5.0	MEDICAL SUPPLIES														
5.1	Supply and delivery Medical Supplies	1.00	lot												_
-	Emergency eyewash and safety shower station repositioning														
	Purchase of Gown Hook	6.00	pcs												
	Purchase of Shoe rack	1.00	lot							1					+
L	Purchase of Medical trash bin; waste foot	3.00	unit												+
	Purchase of Stainless Steel Medical Hospital Laboratory Scrub		unit	+											+
	Purchase of Stainless steel shower basin	1.00	unit												
6.0	SMALL REPAIR WORKS		1.1												4
6.1	Small Repair works	1.00	lot	-						+					+
L	Remove and Replace door knob @ Template Room			1	I	1		1	1			I	L		

	Kwikset Door knob	1.00	unit								
	Remove Exhaust fan and Seal off with board	2.00	unit								
	Repair damaged Ceiling furring	1.00	lot								
	Provision of hole Opening for water supply	2.00	opening								
	Provision for Pass Box (Cheaping and repair)	1.00	unit								
7.0	PLUMBING WORKS										
7.1	Re-piping works for the existing emergency eyewash and safety shower station and water supply (Plumbing Works)	1.00	lot								
	Emergency eyewash and safety shower station repositioning										
	Water Fittings	1.00	lot								
	Provision hole Opening for water supply	2.00	opening								
	1/2" dia Tee G.I	1.00	рс								
	Teflon Tape	1.00	roll								
	Flexible Hose	1.00	рс								
8.0	Other work items required but necessary to complete (Plea	se identify)									
	GRAND TOTAL COST										
	Prepared by:				Submitted by:						
						· · · · ·					